BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/OW/WORK_INDENT18986/CALL-2

APPROVED SCHEDULE - B

[redacted]E-PMT/03/2015-16, Date: 22.01.2016

[redacted] Tractor and Labour for Removal of Silt and Over burden Earth in Ward No. 11 (Kuvempunagara), [redacted]ura Sub Division.

[redacted]	Description	Unit	Approved Tender Rates of Sudhakar Reddy K		
			In Figures		In Words
[redacted]	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	83.16	173533.30	Rupees Eighty Three and Sixteen Paise Only
[redacted] 3697.78	Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed etc complete as per specifications and directions of engineer in charge of the work	Cum	192.24	710861.23	Rupees One Hundred Ninety Two and Twenty Four Paise Only
[redacted] 5784.52	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc complete as per specifications and directions of engineer in charge of the work	Cum	105.70	611423.76	Rupees One Hundred Five and Seventy Paise Only
				1495818.29	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

17/05/16

17/05